

**MODIFICATIONS TO TUCSON WATER STANDARD WATERWORKS SPECIFICATION
NO. 0205, EARTHWORK**

0205.0301 General.

ADD THE FOLLOWING TO PARAGRAPH THREE:

The Contractor shall submit an application for construction water a minimum of two (2) working days prior to use of said water.

0205.0302 Excavation.

(C) Construction Elements.

(3) Surplus Material.

CHANGE PARAGRAPH ONE AS FOLLOWS:

Unless otherwise indicated on the project plans or specified in the special specifications, surplus excavated material shall be removed from the job site and disposed of by the contractor in a manner approved by the Engineer and in accordance with the requirements of City of Tucson/Pima County Standard Specifications for Public Improvements.

0205.0303 Structure Excavation and Structure Backfill.

(C) Construction Elements.

(2) Backfill

(a) Placement of Backfill:

CHANGE PARAGRAPH TWO AS FOLLOWS:

Backfill material shall not be placed against cast-in-place concrete structures until the concrete has developed its full design strength.